

~~SECRET~~

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3  
Copy No.

**CONFIDENTIAL**  
**GEOGRAPHIC INTELLIGENCE REPORT**

BAKU-ASTARA COASTAL REGION



CIA/RR-GR-37

7 January 1954

NIMA Declassification/Release Instructions on File

**CENTRAL INTELLIGENCE AGENCY**  
**OFFICE OF RESEARCH AND REPORTS**

DOCUMENT NO. \_\_\_\_\_

NO CHANGE IN CLASS.

DECLASSIFIED

CLASS. CHANGED TO: TS SC

NEXT REVIEW DATE: 01/89

AUTH: HR 70-2

DATE: 9/13/71

**CONFIDENTIAL**

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3  
Copy No.

S-E-C-R-E-T/CONTROL

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Copy No.   

GEOGRAPHIC INTELLIGENCE REPORT

BAKU-ASTARA COASTAL REGION

CIA/RR-GR-37

7 January 1954

NOTICE

This material contains information affecting the national defense of the United States within the meaning of the espionage laws Title 18, USCA, Secs. 770 and 771, the transmission or revelation of which in any manner to an unauthorized person is prohibited by law.

CENTRAL INTELLIGENCE AGENCY

Office of Research and Reports

**CONFIDENTIAL**

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

S-E-C-R-E-T/CONTROL

CONTENTS

	<u>Page</u>
I. Introduction	1
II. Terrain	3
A. Northern Area	4
B. Central Area	5
C. Southern Area	6
III. Hydrography	10
A. Offshore Characteristics	10
B. Inland Characteristics	32
C. 1. Northern Area	32
2. Central Area	33
3. Southern Area	37
IV. Vegetation	39
V. Climate	22
A. Temperature	22
B. Precipitation	23
C. Surface Winds	25
D. Visibility and Cloud Cover	21
E. Length of Day	25
VI. Settlement	25
VII. Ethnic Composition of the People	31
VIII. Transportation	32
A. Railroads	32
B. Roads	34
C. Water Transport	37
IX. Military Installations	38

ILLUSTRATIONS

Figures through 13 . . . . . Pages 11-18

MAPS AND AERIAL PHOTOGRAPHS

1. CIA Map 12979. Talysh-Azerbayzhan SSR, 1:1,250,000 \*
- ✓ 2. AMS Series 501. N 39°10', N 39°20', N 39°30', 1:250,000
- ✓ 3. 39 aerial photographs of the Caspian coast.

\* Map 12979 is no longer available. It is a reduced reproduction of the eastern half of the Soviet map AZERBAYDZHANSKAYA SSR 1:600,000 GUGK, Tbilisi, 1952 -- which is merely a general orientation map.

S-E-C-R-E-T/CONTROL

## THE BAKU - ASTARA COASTAL REGION

I. Introduction

This study is an analysis of selected geographic aspects of the Baku - Astara Coastal Region of the Azerbaijan SSR. The region is located along the western shore of the Caspian, stretching from Baku southward to Astara on the USSR - Iranian border. It extends inland for a distance of approximately 15 miles.

II. Terrain

The Baku - Astara Coastal Region can be divided into three major physical areas, namely (1) the northern area, which takes in all of the region north of the Pirsagat Valley and which includes a narrow coastal plain backed by outliers of the Great Caucasus Range, (2) the central lowland which extends south from the Pirsagat Valley to Lenkoran', and (3) the southern area which includes a marshy coastal belt between Lenkoran' and Astara backed by the Talysh Range.

A. Northern Area

The northern area consists of two sub-areas -- a narrow, sandy coastal plain and the much larger inland sub-area of rolling highlands with numerous volcanic hills and salt lake basins (Figure 1).

The coastal strip between Baku and the Pirsagat River Valley is characterized by a narrow beach with sweeping bays, sharp capes, and offshore volcanic or sand islands. The gradual lowering of the level

of the Caspian in recent years has resulted in a considerable increase of newly exposed, poorly drained land near the water's edge. Southward from Mys (Cape) Shikhov the coastal lowland lies below mean sea level and varies in width from about 2/3 of a mile to 5 miles.

Pre-World War II data described Mys Shikhov as a cape where hills came down to the edge of the sea. However, more recent information indicates that as the level of the Caspian lowered a narrow beach emerged between the hills and sea, and a former inlet into southern Baku has disappeared.

Directly west of the hilly southern part of Baku is Dolina Yasamal, the north-south valley which lies below sea level. Dolina Yasamal flares out to the southwest where it is occupied by 3 interconnected salt lakes. The salt lakes are surrounded by a lowland, which consists of an extremely narrow strip on the inland side and a somewhat wider, unbroken bar seaward. Elevations along the sandy bar between the lakes and sea vary from 35 feet above sea level to about 90 feet below. Two channel markers are located on the bar southeast of Ozero Krasnoye. East of Puta is Gora Lok Baton, a circular depression-topped, mud volcano that rises about 300 feet; it is surrounded by an irregular marshy lowland which is below sea level. Lok Baton is a dormant volcano which erupted as late as 1935. From Puta Village, the low-lying coastal belt extends southwestward to the village of Sangachly. Along the edge of the sandy beach elevations are as low as 90 feet below sea level. Elevations of the salty marsh land toward the interior increase gradually

to sea level and then rise abruptly on the flanks of isolated mud volcano outliers of the Caucasus Mountains.

South of Sangachiy, the shoreline has 3 bays, one north of Mys Sangachal, one between Mys Sangachal and Mys Alyat-Kosa, a third, on which the town of Alyaty (Alyat) is located, southwest of Mys Alyat-Kosa. The cape and bay part of the lowland coast is a dry area marked by stretches of sand dunes, ravines reaching to the sea, a profusion of sandy hillocks north of Mys Alyat-Kosa, and steep natural embankments (sea terraces) south of Mys Sangachal and near Alyaty. Elevations range from 35 feet below sea level to sea level. Slopes are gentle. Widths of the lowland vary from about 1 mile near Sangachiy to approximately 4 1/2 miles at Mys Alyat-Kosa.

Four islands and an oil well platform lie athwart the entrance to Baku Bay. From east to west the islands are : Ostrov Peschanyy (the largest), Ostrov Vul'f, Ostrov Plita, and Ostrov Nargin. All four islands are partly sandy. Ostrov Nargin has a relative relief of about 125 feet and has a light house and a number of channel markers. Ostrov Plita also has a light house. Northeast of Mys Shikhov offshore oil wells lie close to the mainland, and oil drilling operations are being conducted on and around Nargin Island.

Midway between Mys Sangachal and Mys Alyat-Kosa and about 7 1/2 miles offshore is the low flat island, Ostrov Duranayy. Two low islands lie directly east of Mys Alyat-Kosa; the first is less than a mile from the mainland, and the second, Ostrov Bulla, which has a

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

light on its eastern shore, is about 7 1/2 miles from the mainland. Ostrov Glinyanyy is a pan-shaped island about 2 miles directly west of Alyaty. The western part of the island is low and sandy; the relative relief is 95 feet, a range from -85 feet to 10 feet about sea level.

Inland from this coastal strip are rolling highlands containing numerous circular, steep-sided volcanic hills, salt lake basins, intermittent stream valleys, and precipitous canyons reaching to the sea.

The salt lakes, which are fed by intermittent streams, lie in a series of depressions 1½ miles west of Baku. The more prominent hills adjacent to the lowland rise to elevations of 700 to 1300 feet. Some of these hills are mud volcanoes with fairly steep slopes which in places become precipitous. Many of these hills have been deeply scarred by ravines. Prominent peaks along the coast to the south of Baku include Gora Lok-Baton (Figure 2), about 300 feet high; Gora Takhbaly-Kaya, between Puta and Kara-Dag, 1,245 feet in elevation; Gora Tornegly-Akhtarma, 385 feet; and Gora Osman Bogy Dag (Gora Daligli on the AMS map), exceeding 1,245 feet; Gora Kyagniza-Dag, a circular mountain with a thumb-like southern extension, 1,310 feet; Gora Gichix-Dag, 660 feet; Gora Kir-Dag, 860 feet; Gora Kotur-Dag, a peak with a long, knife-like ridge on the north side that lies 3 miles northeast of Alyaty, 720 feet.

Toward the interior of the Baku - Astara Region peaks become higher and closer together. The two highest peaks are Gora Taurayy,

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

9 miles west of Sangachly, 1,315 feet; and Gora Kalender-Tapa, a mud volcano 6 miles north-northwest of Gora Tauragay, 1,730 feet high. Slopes of 50 to 80 percent are common in the west. The southern edge of the highland area ends abruptly at the Pirsagat River.

B. Central Area

The central area is basically a level lowland which extends south from the Pirsagat Valley. Near Frishibinskoye the lowland begins to taper until at Lenkoran' it consists of a 5-mile strip between the Talysh Range and the sea. The area includes the wide flood plain and delta of the lower Kura. The major exceptions are a few isolated low hills and the hilly area immediately south of Navagi, which is an outlying spur of the Caucasus Mountains. Practically all of the lowland lies below the mean level of the Black Sea. The major types of lowland terrain features include swamps, marshy meadows, streams with imperceptible divides, an extensive area of sand dunes, low narrow ridges, lakes, and streams. Where irrigation is available some of the land is intensively cultivated. Beaches, capes, bays, deltas, bars, spits, and offshore islands are common coastal landforms.

From Navagi (about 100 feet above sea level) the Pirsagat River valley slopes gradually to the Caspian shore (85 feet below sea level). Southeast of Navagi, the valley constricts to a width of 3 miles then fans out again. Small patches of sand and marshy meadowland are features of the lower valley.

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

The prominent highlands between the Pirsagat Valley and the Alyaty - Ali-Buyramli railroad are dominated by Gora Bol'shoy Mishov, a mud volcano mountain deeply scarred by innumerable canyons and ravines. This peak rises more than 960 feet above the nearby lowland, and has slopes of 40 percent in many places. The rough hill land extends eastward from Gora Bol'shoy Mishov and culminates in the circular mud volcano, Gora Kalmas, which has a height of 655 feet. It, too, has steep slopes (over 50 percent) and is deeply cut by numerous gorges.

The coastal configuration south of Alyaty to the Kura delta consists of wide sweeping bays, 2 old capes (Mys Pirsagat and Mys Byandovan), and a new one south of Mys Pirsagat -- formed recently as the sea receded. Sandy beaches and marine terraces prevail along the Alyaty - Kura coast. A series of small, low islands are also encountered at various distances offshore. Both Mys Pirsagat and Mys Byandovan are distinctive landmarks above the adjacent sea and lowland. The relative relief of Gora Khaman-Dag at Mys Pirsagat is about 260 feet, from 65 feet below sea level to 195 feet above. The hill at Mys Byandovan rises from minus 80 feet to 155 feet above sea level; the relative relief is thus 235 feet. Near the village of Byandovan, midway between these 2 capes, Gora Boz-Dag (Gora Akh-Zyvyr) exceeds 390 feet in elevation and has a total relief of 475 feet. A ridge extension of Gora Boz-Dag reaches the coast at Byandovan and continues south to the small hill Gora Zayach'ya which has a relative relief of 110 feet. Nowhere else along the shore from Alyaty to Lenkoran' do elevations exceed mean sea level.

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

The Kura delta projects southeastward about 10 miles beyond an otherwise straight portion of the coast line. Most of the delta is swampland which lies 65 to 80 feet below sea level. A sandy bar separates Ozer' Yakopinskoye from the sea, and in many places marine terraces parallel the shore. The arms of the Kura River are often paralleled by natural levees.

South of the Pirsegat River and behind the coastal strip is a 9-mile wide belt containing sand dunes, salt pans, and passable swamps, which extends to within a few miles of the Kura River. In addition to the dunes, other major relief features are mud volcanoes and extinct volcanoes. Average relative relief in this sandy waste land is about 10 feet.

West and south of the sandy coastal zone is the Kura - Akusha valley occupied by a large maze of streams, irrigation canals, drainage ditches, swamps, dikes, levees, as well as a few lakes. Elevations are generally low, and relative relief is significant only along river bank levees, the steep-sided old stream channels, or on a few small mud or extinct volcanoes. The volcanic ridge 4 miles east of Sal'yany, with points 130 feet above the adjacent flood plain of the Kura, is the site of many old burial mounds 3 to 30 feet high. Cora Kyursanga, a circular hill 12 miles directly west of Byandovan, rises 250 feet above the surrounding plain and has 40 percent slopes. It has a dense pattern of deep dissection.

The exact delimitation of the coast between the mouth of the Kura and Lenkoran' cannot be ascertained, but it is known that much

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

low land has recently been exposed by the receding Caspian. Kaliv Imani Kirova, the bay south of the Kura Delta has decreased in size so much in recent years that the former strait west of the island chain Ostrov Ilyinovskiy - Ostrov B. Kulagin - Ostrov Baranki - Ostrov Sars may have disappeared, and the islands are now part of the mainland. A swampy, salty, sandy lowland rings the bay on 3 sides. The spit Durinskaya Kosa, enclosing Kirova Bay to the east, is slightly more than 1 mile wide at its narrowest part and has an average elevation of 30 feet below mean sea level. A sandy beach ridge backed by swampy low land extends from Port M'acha almost to Lenkoran'. On the beach north of Ol'kapaia T'ol'sanee, now extinct, have been thrust 50 feet above the surrounding land. Most of the lowland between the swampy area of Kiriyevskiy Zapovednik and Lenkoran' is devoted to rice cultivation. However, the long stretch of rice fields, with their closely-spaced small check dikes, is interrupted in many places by patches of swamp and meadow land.

#### C. Southern Area

The southern area is divided into 2 distinct sub-areas - the narrow, low, subtropical coastal plain south of Lenkoran' and the rugged, forested Talysh mountains in the west (Figures 3 and 4).

Most of the lowland belt averages about 4 miles in width, but in the south it bulges out to a width of 5.5 miles. The coastal plain lies below mean sea level and has a gentle slope down toward the sea. The Caspian coast line between Lenkoran' and Astara is regular with very few indentations. At the beach the land rises slightly (10 to

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

20 feet) before dropping to the water's edge. From the Lenkoran' (Lenkoranets) River to the village of Kholmili a beach terrace separates the low rice land from the Caspian. South of Kholmili to Astara, an irregular beach ridge in places only a few yards wide is backed by rice fields and by a large impassable swamp which ends 3 miles north of the Iranian border. The Lenkoran' River delta is a sandy projection with a small island lying between the 2 forks of the river. The beach is also sandy for a distance of nearly 5 miles south of Astara City.

Relative relief is slight throughout the lowland (Figure 5). The most prominent terrain features are a number of high banks along sections of the various streams, and old terraces, some of which rise as high as 100 feet above the Caspian.

Although the eastern edge of the Talysh Range is sharply defined there is a noticeable degree of difference in the abruptness with which the various portions of the range rise from the coastal plain. In the extreme north the rise of the foothills above the plain is quite gradual. Five miles west-northwest from Lenkoran' a hill rises 760 feet above the nearby lowland in a horizontal distance of 2,295 feet resulting in an average slope of 34 percent.

South of Lenkoran' the Talysh Mountains rise abruptly from the coastal plain (Figure 6); several peaks tower more than 1000 feet above the plain. A mountain directly west of the coastal village of Khutarki (located 1/2 mile north of Tazakend) has an elevation of

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

1,145 feet. Slopes are greater than 40 percent and numerous ravines radiate from the top. Five miles to the south a mountain between the lower Talysh River and the coastal plain is 985 feet above sea level and has slopes in excess of 50 percent. Slightly over 1 mile north of the Iranian border, another steep-sided mountain rises 1,065 feet above the lowland.

South of Lenkoran elevations increase rapidly from about 2,500 feet at a distance of 3 miles from the plain to 4,000 feet at a distance of 9 miles, and to 5,000 feet at 17 miles inland. Elevations greater than 6,000 feet are found frequently along the crest of the Talysh chain which marks the Soviet-Iranian boundary. Deep gorges, vertical cliffs, and steep slopes are characteristics of the eastern Talysh Mountains. With few exceptions, the stream valleys are deeply entrenched and are very narrow. However, the flood plain of the lower Lenkoran River, the width of which exceed 1/2 mile in places, extends 7 miles into the mountains. East of Pensur at the confluence of the Talysh and Qalbu Rivers, a plain 1 mile wide and slightly more than 1 mile long has been formed and is connected with the coastal lowland by a narrow water gap. The lower Astara Valley (Figure 7) has a width of about 1/2 mile as far as Ordzhmagly, 2-1/2 miles west of the coastal plain.

### III. Hydrography

#### A. Offshore Characteristics

Information concerning the pronounced drop of the Caspian Sea Level indicates the configuration of the coastline and offshore

islands has changed significantly in recent years. Lack of detailed information, however, precludes accurate analysis and description of the changes.

In 1949 the level of the Caspian Sea was reported to be 92 feet below mean sea level. Although the Caspian is a tideless sea, it is subject to annual fluctuation. The range throughout the year is from 12.5 to 21.5 inches. The highest level occurs near the end of June, and the lowest level occurs between January and March.

The following postwar descriptions are for nearshore approaches to a number of beach areas between Baku and Astara. The approach to the beach area west of Mys Shikhov has flat-bottomed slopes, a submerged offshore bar immediately in front of the beach, light surf, and drift to the west. The approach to the beach east of Mys Sangachal has a flat bottom, a rocky reef 0.5 mile offshore in the south, moderate surf, and drift to the south. The approach to the beach north of Mys Vilyayt has flat-bottomed slopes, moderate surf, and drift to the south. Moderate surf, and drift to the south. The approach to the beach north of Mys Pirseagat has flat-bottomed slopes; Ostrov Glinyanyy is about 3 miles offshore, and sunken rocks are located about 1 mile offshore; surf is moderate; drift is to the south. The approach to the beach north of Mys Byandoven has flat-bottomed slopes, rocky shoals extending 1 mile offshore, moderate surf, and drift to the south. The approach to the beach south of Mys Byandoven has flat-bottomed slopes, a rocky shoal 6 miles off the northern end, moderate surf, and drift to the south.

- 31 -

S-E-C-R-E-T/CONTROL

Approved For Release 2001/09/03 : CIA-RDP79-0109A000500030001-3

The approach to Kurnekaya Kosa has flat-bottomed slopes, scattered shoals, moderate surf, and drift to the southwest. The approach to Ostrov Sara has flat-bottomed slopes, light surf, and drift to the southwest. The approach to the beach area north of Astara has flat-bottomed slopes, sandy shoals 0.5 mile offshore in the north and 1.5 miles in the south, moderate surf, and drift to the south.

#### B. Inland Characteristics

Major hydrographic features in the coastal zone from Baku to the Iranian border consist of intermittent salt lakes, which turn into salt pans in summer, marshes, and intermittent streams in the northern area; a dense network of permanent streams, several large lakes, and numerous swamps in the central area; and in the southern area a heavy concentration of springs and mountain streams in the Talysh Range and rivers, swamps, and lagoons in the coastal lowland.

##### 1. Northern Area

On the west side of a beach ridge a few miles southwest of Baku, 3 interconnected rectangular intermittent salt lakes parallel the shore for 9 miles; the average width of the lakes is about 1 mile. Ozero Krasnoye is in the center, and Byvshiy Zaliv Puta (formerly a gulf) is in the southwest. Several other intermittent saline lakes with salt-crusted shores fill shallow depressions west of the coastal lakes and hills. The largest is Solon' Geyuch-Altnu-Chalasi, a salt lake about 3 miles long and 1 mile wide, which is located 8 miles due west of Puta. Steep, natural embankments rise at the northern and

Approved For Release 2001/09/03 : CIA-RDP79-0109A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

southern edges of the lake basin, and rocky slopes with even grades border the northeastern portion. Three other shallow salt lakes are located less than 5 miles north of Salor' Gemish-Altnu-Chalasi.

Most of the small, short, intermittent streams in the coastal zone west of Baku flow into the salt lakes and marshes or disappear into the sandy ground. A small high water occurs in spring. By late summer the water in most tends to be dry. A swamp of indefinite extent borders the northern edge of Kara Lake Baku, and marshy areas with numerous drainage ditches are located west and south of Kars-Dag. An aqueduct which begins at Shish-Kaya follows the lowland between Gora Dzhigilli and Gora Ryegrass-Dag southeastward to the coastal railway. Another aqueduct, 4 miles long, is located between Dzheyrankchmez River and the village of Chair-Dag. Innumerable gullies and ravines mark the mountains and hills north of the Pirsagat River, but permanent streams are entirely lacking.

The first large permanent river south of Baku is the Pirsagat which has its source high on the southern flank of the Caucasus. This stream usually terminates in the sandy, swampy wastes southwest of Alyaty. Only during the spring high water period does the Pirsagat reach the Caspian Sea. The Pirsagat Valley southeast of Navagi contains numerous tributaries and distributaries of the main stream, short disconnected streams appearing and disappearing at random, a number of passable salt marshes, swamps, and cisterns concentrated along the base of the hills flanking the valley to the north and south. A section of the

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-0109A000500030001-3

river north of Gore Kalmas dries up completely during the dry season. All Pirsagat channels follow twisting courses. The average current velocity near Navagi is 1.3 feet per second. In general, the stream banks are low but in 2 places, where the river swings close to hills, it is entrenched between high banks. A number of railroad bridges span the numerous branches of the Pirsagat southeast of Navagi and southwest of Alyaty.

## 2. Central Area

An outstanding characteristic of the rough hill land south of the Pirsagat River is the multitude of high-gradient ravines and gullies which are dry stream beds for most of the year. The hill land also contains springs, some of which are saline, clusters of wells and cisterns, and a small salt marsh at the southern edge of the hill.

The lower Kura floodplain is remarkable for its great number and variety of hydrographic features. The wide, deep Kura River dominates the plain (Figure 3). Countless closely-spaced streams along the Kura flow outward from the main stream in many directions to lowland swamps. Lakes, swamps, and salt marshes are extensive and numerous in the Kura lowland.

The lower Kura has pronounced meanders, high natural levees, ox-bow lakes, man-made dikes, and a long irregular delta where the river branches into several arms before emptying into the sea. The current of the lower Kura is sluggish, averaging from 0.3 feet per second to 1.6 feet per second. At low water the Kura is 400 to 600 feet wide.

and 18 to 30 feet deep. The stream is frequently higher than the adjacent land, and therefore requires protective dikes in many places.

High water overflow usually occurs sometime between March and the end of June. Lesser floods occur from July through September and in the winter. The coastal section of the river does not normally freeze in winter. Sal'yany is the point where the Akusha River, an important arm of the Kura, branches from the main stream and twists its way first southwest and then southeast toward Zaliv Ineni Kirova. Countless ditches also branch out from the Akusha. The Akusha is from 100 to 150 feet wide, 4.5 to 10 feet deep, and has an average velocity of 1.6 to 1.9 feet per second. The regime of the Akusha is generally the same as for the lower Kura with maximum flow occurring in spring and minimum flow in late summer and in winter. The Akusha is bridged in many places.

The extremely dense network of large and small streams and ditches, many of which are diked, could seriously hamper vehicular traffic or movement on foot. The drainage and irrigation ditches frequently form small rectangles a few hundred yards wide and less than 1 mile long. In the spring hundreds of temporary ponds and lakes result from overflow of the Kura and secondary streams.

A number of salt lakes are located on both sides of the Kura. About 7 miles west of Sal'yany is the large salt lake Ozero Makhmudchala (the northern Akh-Chala on the AMS map) and about the same distance southwest of Ozero Makhmudchala is a large swamp lake, Ozero Akh-Chala which is navigable for small boats. Both lakes fluctuate in size and are bordered by swamps and

salt marshes. The outlet of Makhmudchala is the Armyanka River which flows southward at a rate of 0.3 to 3.2 feet per second to and through the large swamp Kirovskiy Zapovednik (a reserve for water fowl and other birds).

Another salt lake lies in a sandy depression midway between the Kura at Sal'yany and the ridge about 3 miles to the east. The 3-mile long lake contains several islands three of which are topped by old burial mounds. On the Kura delta north of the river is the pouch-shaped lake Ozero Yakopinskoye which is bordered by sand on 3 sides. At Neftechala there is a narrow lake 4 miles in length. A railroad bridge and 2 hard-bottomed fords 1.6 feet deep cross it. Large expanses of passable salt marsh which vary in extent in different seasons are located (1) on the sandy coastal belt between the Pirsagat and the Kura, (2) straddling the Kura River on the delta south of Ozero Yakopinskoye, (3) from Neftechala north to the Kura, (4) about 6 miles southeast of Sal'yany (5) north of and adjacent to Ozero Akh-Chala, and (6) along the old north and northwest shores of Zaliv Imeni Kirova. Of the many reed-covered passable swamps, Kirovskiy Zapovednik is the largest. It extends in an ever-widening crescent from the southern shore of Ozero Akh-Chala to the old shores of Zaliv Imeni Kirova and is about 2 feet deep. A passable swamp (1 to 2.2 feet deep) is located at the northeastern edge of Ozero Akh-Chala. Swamps also occupy the eastern half of the Kura delta and the northern part of Kurinskaya Kosa. Many smaller swamp and marsh patches are distributed throughout the Kura Lowland.

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Potable water is not abundant in the Kura lowland. An aqueduct joins the towns of Neftchala and Bol'shoy Criat.

3. Southern Area

Between Kirovskiy Zapovednik and the Iranian border the hydrographic features of the coastal lowland consist of streams, lakes, marshes, swampy lagoons, and rice paddies. The streams flow from the mountains heavily loaded with alluvial material, which they deposit onto the plain in the form of fans at the mountain base. Between Novyy Alwyd and Girdani extends a long, wide rice field filled with small paddies, dams, ditches, and transverse streams, and interspersed with patches of swamp and meadow. Three lakes, 7 to 10 feet deep, surrounded by a reed-covered swamp are located between Port Il'icha and Lenkoran'. Except for a 4-mile long, 5-foot deep, swampy lagoon north of Astara, rice fields, reed or forest swamps and meadows occupy most of the land between Lenkoran' and the Astara River.

The swamps and swampy lakes, which fluctuate in size, are fed by streams, underground seepage, and frequent rains. Most of the swamps and lakes are salty. The coastal plain is generally deficient in good drinking water during the drier season. Springs and wells are located close to the mountain base. The springs and wells normally have a small discharge of good quality water.

In the Talysh Mountains springs are much more numerous and are the sources of many streams. Heavy precipitation in the mountains feeds the numerous streams which empty into the Caspian Sea or into the

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

bordering lowland. The drainage pattern is dendritic with the main streams having a general eastward orientation. Rivers have steep gradients and narrow river-walled valleys. High water on the rivers usually occurs in fall and winter, with low water in late summer. The Talyshay, a large stream flowing from the north part of the Shingir Ridge, has a velocity varying from 1.4 to 3.2 feet per second. The valley is narrow in the highlands and its banks bordered by high stream banks in the lowland. Roads are rare, but the stream is often bridged at a number of places. The Balady-Chay, on the south, flows narrow streams in the mountains but broadens in the Talysh lowland and then widens through the coastal plain. In the plain it bends around the town of Balady, flows north at 0.3 feet per second through a vegetable garden area, and finally cuts eastward through a swamp to the sea. Numerous bridges cross it. The Laker-Chay begins in the eastern mountains, flows east between high banks across the forested Talysh flanks and into the swampy basin of Lenkoran. It then flows north toward the Balady-Chay at a velocity of 1 foot per second.

The Lenkoran' (Lenkoranka) River grows rapidly as it flows eastward, collecting waters from its many tributaries. Near its junction point with the north-flowing Laker-Chay, the steep wooded sides of the Lenkoran' River Valley broaden out to a valley floor about 750 yards wide. At the point where the Lenkoran' spills into the lowland, the velocity is 1.6 feet per second; its charge

frequently braided. Steep banks border sections of the channel. At the sandy delta, the river forks, forming 2 mouths. A number of bridges and ferries cross the Lerkoren, but there are also long stretches with no suitable crossing sites. A major tributary of the northeastern flowing Yezaryal is the Sayfilar, 6 miles northwest of the town of Lerkoren. The velocity of the Yezaryal is 6.6 feet per second. West of Shekaran, the northeastward-flowing Chaku and Targayayu Rivers converge to form a small floodplain pocket. The enlarged river then breaks through the mountains into the lowland where its waters are distributed in the rice fields and swamps. The current velocity of the lower Targayayu is 2.6 feet per second. Several bridges span the Targayayu in the highlands, but none are shown crossing the Chaku. A stream with a velocity of 2 feet per second enters the western side of the swampy lagoon which lies north of Astara. The outlet to the sea from the lagoon is through the beach ridge at Kalbaigna.

The southernmost river of eastern Transcaucasia is the Astara-Chay which coincides with the Soviet-Iranian frontier (Figure 9). The upstream portion of the Astara-Chay valley is narrow with high, steep sides. The river's velocity is 13 feet per second. The only bridge-crossing is located at the town of Amara.

S-2 CONTROL

#### IV. Vegetation

In the northern part of the region dry-steppe vegetation, consisting mostly of sparser grasses and low scattered shrubs, predominates (Figure 1).

Leather grass, fescue, and bromé are the principal grasses while wormwood is the characteristic shrub. The chief vegetative period occurs

in spring and early summer, when the plants become bright green, flower, and reach knee-height growth. In summer, however, many of the plants die.

The widely-spaced individual plants of the surviving vegetation turn dull green or brown. The open character of the vegetation permits unhampered movement. A second brief vegetative period occurs at the time of the fall rains. Some plants remain green throughout winter.

The dry-steppe vegetation serves as winter fodder for sheep, goats, and other livestock.

In the central part of the region, dry-steppe and salt marsh vegetation are present in the area northeast of the Kura River. In addition to the usual steppe plants, however, dense impenetrable thickets of tamarisk are characteristic. The tamarisk is a drought-resistant scrub tree, growing to heights of 10 to 12 feet. The undergrowth in the thickets is comprised mostly of the Russian olive, a low, stiff, prickly shrub.

The character of the vegetation changes along the Kura River. On the moist banks, the steppe vegetation is replaced by high, closely spaced tufts of Bermuda grass and occasional small stands of poplar, willow, and other small deciduous trees. In the lowlands along the Kura and the Akusha Rivers crops are grown by irrigation. Southeast of the

S-2 CONTROL

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Akusha River irrigation system is an extensive area of reed-covered swamp which reaches from Ozero Aks-Chala to the old shore of Zeliv Tazni Kirova.

In the northern part of the region, dense deciduous forests are typical, especially in the Talysh Mountain (Figures 6 and 15). In the moist Lenkoran' Lowland, the forests are interspersed with relatively large areas of marsh growth, as well as cultivated vegetation and meadow grasses. The varieties of trees comprising the forest differ with elevation. In the Lenkoran' Lowland, bearded alder, poplar, pear, crab apple, and other small trees are characteristic. The trees grow in thick profusion. Also common are vines such as greenbrier, silver vine, and ivy. In many areas the dense forests entwined with vines are impassable. Iris and tripe are the most common marsh plants in the lowland. The cultivated vegetation consists mostly of fruit trees and rice.

On the lower slopes of the mountains, chestnut-leaf oak is the predominant tree. The generally dense understory of the oak forests is comprised chiefly of Persian parrotia, hornbeam, silk tree, and persimmon. On the high slopes the characteristic forest tree is the peach, while evergreen shrubs -- rhododendron, laurel-cherry, and holly -- usually comprise the upper growth.

Salt marsh and sand plants are the characteristic vegetation along the entire sea coast and offshore islands. Salsola grass grows in scattered clumps on the sands closest to the sea and on part of the offshore islands. Further inland from the shore, small series of

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

tamarisk, wild rye, and black wormwood are the typical growth, especially on the dunes. Sea lavender occupies the sands in the dry basins near the sea.

V. Climate

The climate of the Baku - Astara Coastal Region is characterized by hot summers and moderately cold winters. Precipitation is generally scanty, except in the Lenkoran' Lowland and Talysh Mountains. Climatic data for the region were obtained from two stations, Baku and Lenkoran'.

A. Temperature

Temperatures in the region are not as extreme as they are in the interior of the Transcaucasus to the west, for the Caspian Sea has a moderating influence, bringing cooler summers and milder winters. The average annual temperature in the region is about 57°F. Both Baku and Lenkoran' have mean monthly temperatures of approximately 79°F for July, the warmest month, and 33°F for January, the coldest month. On some winter days the temperature rises above 50°F. Despite the mild winters frosts are not uncommon in January and February. Severe cold is rare, and in most years, ice is absent along the coast. In summer daytime temperatures above 90°F are common in July and August, but cool nights during which temperatures drop 20 to 30 degrees are the rule.

With the low temperatures of winter the relative humidity on the Baku - Astara coast is at a maximum. In fall the relative humidity on the coast will be fairly high on many days because of rainy weather.

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

In summer the air is very dry and hot, with even the early morning hours frequently having low relative humidities.

B. Precipitation

Precipitation is generally scanty in most of the Baku - Astara Coastal Region. In the part of the region lying to the south of the latitude of Kyzyl-Agach, however, the precipitation increases and in the Lenkoran' Lowland and Talysh Mountains it is abundant. The average yearly precipitation of 50 inches for Lenkoran' is in sharp contrast with the average of 7.3 inches for Baku. In both Baku and Lenkoran' the maximum occurs in fall, and the minimum in summer. In November, the wettest month, precipitation averages 8.5 inches in Lenkoran' and 1.2 inches in Baku. Mud and soft ground conditions are characteristic during the fall rainy season. In July, the driest month, Baku averages only 0.2 inches and Lenkoran' 1.9 inches. Dry, dusty ground is typical in summer, especially along the central and northern sections of the coast. In the drier areas precipitation occurs on 2 to 3 days each month varying with the season. In the more humid areas it occurs on 3 to 11 days each month. In the coastal lowlands, some of the winter precipitation is in the form of snow. An intermittent snow cover from 2 to 6 inches deep is sometimes present for a few days. In the Talysh Mountains, however, snowfall is common throughout winter, and the snow cover may exceed 3 feet in depth in some places.

C. Surface Winds

North winds prevail throughout the year at Baku and west or northwest winds at Lenkoran'. The winds along the northern part of the

coast are usually strong, often exceeding 33 miles per hour in velocity. Gales are characteristic at Baku in all seasons, but in summer the gale frequency reaches as high as 18 per month. Lenkoran' has many calm days, even in summer. In winter west winds at Lenkoran' are often associated with rapidly rising temperatures. In summer the area within a few miles of the coast has pleasant afternoon sea breezes while off-shore winds predominate at night.

D. Visibility and Cloud Cover

Fall, winter, and early spring are the cloudiest parts of the year. The number of days when at least 0.9 of the sky is cloud covered averages 13 to 20 days a month from October through March. Summer has the least cloudiness. In August, the month with the least cloudiness, the average is 4 to 7 cloudy days. Low, often continuous sheets of stratus clouds typify the cloud cover in fall and winter, while a broken cover of cumulus is usual in spring. Summer cloudiness usually consists of the cumulus type.

Fogs and dust are the principal restrictions to visibility along the coast. In contrast to the interior of the Transcaucasus, fogs may occur along the Caspian Sea coast throughout the year. The frequency of fog in winter, however, is higher than in summer. The January average is over 3 days and the July average is less than one. Dust is common over the Caspian Sea coast throughout the year. Even when the sky is clear of clouds, the high content of dust in the air gives a hazy appearance to the atmosphere. Although fall and winter rains help to settle the dust, they likewise reduce the visibility.

E. Length of Day.

Daylight lasts for approximately 9 hours in December and increases steadily to 12 hours in March. The longest days are in June, when there is an average of 16 hours of daylight. The length of day decreases at the rate of about 1 hour a month thereafter.

VI. Settlement

The population of the Baku - Astara Region is moderately dense, but unevenly distributed. The highest densities of 125 or more persons per square mile are found in the immediate vicinities of the two cities of Baku and Lenkoran'. In the foothills of the Talysh Mountains west of Lenkoran' densities are more moderate, ranging from 62 to 125 persons per square mile. Most of the remainder of the region -- the belt along the Kura and Akusha Rivers, and the foothills of the Caucasus in the northern part of the region -- is characterized by densities of 25 to 62 persons per square mile. Densities below 25 per square mile are encountered only in the marshy lowland which cuts across the region in a northwestern direction from the western side of Zaliv Imeni Kirova, and in the sandy coastal stretch between Alyaty and the mouth of the Kura River.

The northern area of high population density in the region stretches from Baku about 12 miles southwestward to the vicinity of Shongar, Kyzyl-Tepe, and Kara-Dag. The eastern strip of this area, which extends northward from Mys (Cape) Shikhov to Mys Bailov, is actually a southern extension of the city of Baku. Throughout this strip buildings and oil towers are intermixed with little discernible pattern. West of Baku

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

numerous scattered settlements are found, usually at intervals averaging less than 2.5 miles. The settlements here are small, even the larger ones consist of fewer than 200 inhabitants. The larger settlements are usually located at focal points along the main transportation arteries -- the paved roads and the railroad; whereas the smaller workers' settlements are scattered throughout the oil fields. In addition to these inland settlements there is a string of about a half dozen tiny fishing villages distributed along the coastline of this area. Most settlements are just irregular conglomerations of buildings. Some settlements have experienced growth in recent years. Kara-Tag is reported to have expanded considerably in size since World War II. A new residential area of one and two-story houses has been built and is occupied mainly by Russian oil workers.

In the area extending southward from Shongar and Kara-Tag to the east-west railroad between Alyaty and Ali-Bayramli the density of population decreases noticeably. Settlement consists primarily of numerous temporary camps, about 2.5 to 3 miles apart, that appear to be used for housing oil workers. Most are irregularly shaped clusters of a half dozen or dozen small buildings. These settlements are invariably located on the patches of low level land that are scattered in the hilly terrain. Generally one or more cisterns have been constructed near each of the settlements to provide water for the inhabitants.

In the northwest corner a slightly different settlement pattern appears in the vicinity of Khan-Kuli and Beyuk Kaftaran. This area is the winter headquarters for nomadic herdsmen. In summer these herdsmen

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

drive their herds northwestward to pastures at higher elevations of the Caucasus. The numerous isolated shacks which appear at fairly regular intervals along the railroad are probably shelters for maintenance crews. Fishing villages, which are usually located at the heads of the shallow embayments, are also scattered along this part of the coast.

In the broad lowland along the Pirsagat River the settlement pattern also changes abruptly. Settlements become fewer in number but larger and more compact. Before World War II the two largest, Navagi and Alyaty, each consisted of about 2,000 to 3,000 inhabitants. Navagi is located in the middle of an extensive grain area. Two miles southeast of Navagi is the Beriya (probably renamed by now) State Farm, which specializes in the production of grain. At-Bulakh (a town on the railroad 1 mile north of Mirzali) is an oil settlement whereas the importance of Alyaty appears to be derived from its function as a minor landing. The latter settlement has storage warehouses and good rail and road connections inland. A small sawmill is located nearby, apparently to process timber that is brought in by sea. Alyaty also includes a hospital and fishery. The hilly terrain between Navagi and the Alyaty - Ali-Bayramli railroad to the south also provides permanent sites for a number of yurtas (dome-shaped tents used by nomadic herds-men).

In the area between the Alyaty - Ali-Bayramli railroad and the Kura River the settlement pattern again changes. Settlement becomes localized almost entirely in the western half of the area, while the mixed sandy

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

and marshy eastern half is virtually uninhabited except for the oil field area near Pirsagat and a few small fishing villages directly on the coast (Figure 11). Khidyrly, 1 mile northwest of Pirsagat, is a mixed settlement of oil workers and livestock herders. The buildings in Khidyrly are constructed of clay, and for the most part are without windows. In the western half of the area the population is concentrated in small settlements about 3 to 5 miles apart. Most of the settlements are irregular clusters of buildings that form units of a state cotton farm. However, the three collective farm villages in the center, Novokhaladzh, Challa, and Bashirabat (1 mile southwest of Challa), exhibit shoe-string patterns. Most of the settlements are located along irrigation channels.

In the area from the Kura River south to the extensive swamp that runs between the northwestern side of Zaliv Imeni Kirova and Ozek Akschala the population becomes somewhat denser but considerably more concentrated. Practically all of the population is distributed in an almost continuous line of elongated villages along the banks of the Kura and Akusha Rivers. The sole exception to this pattern is found in the area directly south of the Astanly - Bank portion of the Kura River where a number of villages are scattered at intervals of about 3 to 5 miles. A large number of sheds and summer shelters are also distributed throughout the irrigation fields.

The largest town in the area is Sal'yany, located at the point where the Akusha River branches from the Kura. Before World War II Sal'yany had a population of about 15,000 most of whom were Azerbaiydzhanis.

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

and Russians. It is a major cotton ginning center for the Kura Lowland. After the war a prisoner-of-war camp was located here. With the release of most of the prisoners of war in recent years the camp may have been converted for use by penal laborers.

Throughout the Kura and Akusha Lowland economic activity focuses on the production of Egyptian cotton. However, the processing of herring, carp, and sturgeon into caviar and other canned products is also important at the mouth of the Kura where two major fish processing plants are located at Bol'shoy Oriat and Zyuydostovyy Kultuk. Farther to the south are two more plants at Kara-Kush and at the extreme tip of the Kurinskaya Kosa (Peninsula). Neftechala is the center of another expanding oil area. Several new settlement areas were developed here after 1945. According to one report, they consist of barrack-type residences for oil workers and their families. Before the war the town had its own landing pier on the coast, 5 miles to the southeast.

The extensive swamp that runs northwest from the Zaliv Imeni Kirova is devoid of any permanent settlement, but in the coastal lowland that extends along the coast to the south, settlement again takes on the pattern of small villages -- each an irregularly shaped conglomeration of buildings. They are generally distributed at distances of 2 to 3 miles, but there is a somewhat heavier density in the vicinity of Lenkoran' and along the Prishibinskoye - Lenkoran' road, where the population is engaged in the cultivation of rice. The populations of these villages average from 50 to 500 persons, but there are several

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

settlements that materially exceed this average. In the area north of Lenkoran<sup>1</sup> they include Prishibinskoye with about 5,000 to 6,000 inhabitants before World War II and Novyye Alvady and Kyzyl-Agach with about 2,500 or 3,000 inhabitants each. Arkevan, Giga-Chel, Kugl, Balady, and Port Il'itsa have populations of about 1,000 to 1,500. Massaly was in the same population category before the war but recent Soviet small scale maps indicate its present population as being in excess of 2,000.

Lenkoran<sup>1</sup> has a mixed population of Russians, Armenians, and Azerbayzhani totalling about 6,000 to 8,000 inhabitants before the war, but probably somewhat higher now. The town is a port of call for vessels en route from Baku to Iranian ports. However, the bay is so shallow that large ships can not approach closer than three miles from the shore. Most of it is an old town with narrow streets and one-story masonry houses (Figure 12). The industries are focused primarily on the processing of food products such as tea and fish.

South of Lenkoran<sup>1</sup> the larger villages include Archevar<sup>1</sup> with an estimated population of about 2,000, and Pensar and Sheakeran with about 1,250 inhabitants each. There are five villages, Germatuk, Shikhakeran<sup>1</sup>, Khelmili, Shakh-Agach, and Tangerud, which have about 1,000 inhabitants each.

Astara is a border town which extends almost uninterruptedly into Iran (Figure 13). It is important as a center for handling trade with Iran. A fish processing plant is also located there. Before the war Soviet Astara had a population of about 1,000 or 2,000 people. Since

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

then it has probably grown somewhat. A Soviet regiment of about 3,000 men is reported to be stationed there now.

On the forested slopes behind the coastal lowland, the population density drops off abruptly. Villages here are much smaller, probably averaging about 50 inhabitants, and rarely exceeding 100. Distances between settlements average about 3 miles, no more than in other areas principally because there is a noticeable dispersal of the individual households that compose each of the villages. Most of the settlements are located along valley lowlands, or in small clearings on the more gentle of the hilly slopes. The cultivation of tea is a specialized occupation of the inhabitants at the eastern base of the mountains.

#### VII. Ethnic Composition of the People

The population of the Baku - Astara Region is predominantly Azerbaiydzhani. Talysh, Tats, and Great Russians comprise most of the remaining ethnic elements.

The Azerbaiydzhani are largely a rural people, inhabiting the steppes in the Kura Lowland. In recent years, however, many have come to the coastal cities. In physical appearance, Azerbaiydzhani are medium in stature, have long faces, dark hair, and brown eyes. Beards are common, especially among the old men. The Azerbaiydzhani speak the Tatar language, which is similar to the Turkish spoken in Turkey. Tatar, together with Russian, serves as a common tongue along most parts of the coast.

The Talysh occupy the Lenkoran' Lowland and are primarily an agricultural people. The Tats, who are related to the Talysh, live

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

along the coast in the steppes near Baku. The Talysh and Tats resemble the Azerbaiydzhani, but speak the Iranian language or dialects. All three groups are Moslem, and the Azerbaiydzhani have religious ties with Moslem groups of the Near East and Central Asia.

The Great Russians reside in the towns, especially in the administrative and strategic centers. Russians can easily be identified by their greater physical stature and lighter complexions. Armenians, Jews, Persians, and more recent settlers from other parts of the Soviet Union and Europe also inhabit some of the cities in small numbers.

#### VIII. Transportation

##### A. Railroads

The entire north-south extent of the Baku - Astara Coastal Region can be traversed by rail, and a passenger service between Baku and Astara is available daily. The railway net consists of the eastern extremity of the Baku - Batumi line, the main trunk line across the Transcaucasus; the eastern end of the strategic Alyaty - Dzheul'ia - Leninsk line; and the Osmanly Novyye - Astara line which serves the southern half of the coastal region. All of these lines are Russian normal gauge (5 feet). Only the Baku - Batumi line is double-tracked across the coastal region.

About 65 miles of the Baku - Batumi trunk line, from Batumi to Navagi, lie within the Baku - Astara Region. From Baku the line goes northward for about 8 miles to the junction of Baladzhary where it swings southward toward the Caspian coast. The line then runs within a few miles of the coastline to Alyaty. At Alyaty the route turns

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

westward, crosses the coastal region, and continues toward Tbilisi deep in the interior of the Transcaucasus. The line's principal economic function is to move petroleum from the Baku fields to the Black Sea port of Batumi. The railroad is paralleled by an 8-inch pipeline which is now used to transport kerosene. Within the coastal region the pipeline is apparently laid on the surface.

The easternmost 45 miles of the Alyaty - Dzhul'fa - Leninikan railroad line cuts due westward across the Baku - Astara Region. As it runs westward this line diverges from the Baku - Batumi line, until the distance between the two reaches 3 miles at the western margin of the coastal region. Beyond the coastal region the Alyaty - Leninikan line parallels the USSR - Iran border.

The northern 15 miles of the Osmanly Novyye - Astara line lie outside the Baku - Astara Coastal Region. The line branches from the Alyaty - Leninikan line at Osmanly Novyye, 12 miles west of the Coastal Region. The line enters the region approximately 10 miles northwest of the rail junction of Sal'yany. From Sal'yany the line runs along the western margin of the coastal region to Prishibinskoye. The line then leads to Port Il'icha on the Caspian Sea. From Port Il'icha the line runs along the coast through Lenkoran' to the southern terminus at Astara.

From Sal'yany a single-track line extends 21 miles southeastward to Neftechala. This route was constructed primarily to tap the petroleum fields surrounding Neftechala. A narrow gauge (2 feet  $\frac{5}{8}$  inch) line

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

petroleum line leads northward from Neftechala to the Kura river port of Bol'shoy Opiat.

The heaviest traffic of the entire coastal rail net flows over the relatively short rail stretch between Baku and Alyaty and the least amount, over the Sal'yany - Astara segment. Five passenger trains in each direction and several freight and oil trains run daily over the Baku - Alyaty stretch. Only one passenger train in each direction and one to three freight trains daily make the Sal'yany - Astara run.

Passenger trains make average speeds of 20 to 25 miles per hour between Baku and Navagi, about 15 miles per hour on the Alyaty - Dzhul'fa route, and 17 to 22 miles per hour on the run southward to Astara. Oil trains attain similar average speeds but ordinary freight trains average only 10 to 15 miles per hour throughout.

#### B. Roads

The Baku - Astara Coastal Region does not have an effectively integrated road system. Most roads are of local significance only; relatively few are improved. The trip between Baku and Astara however, can be made over improved roads.

From Baku to Alyaty the Baku - Astara road parallels the Baku - Batumi railroad. From Alyaty the road runs in a southwesterly direction to Sal'yany where a bridge provides a crossing over the Kura River. (Prior to World War II road traffic did not move directly to Sal'yany but continued to parallel the Baku - Batumi railroad to Kazi-Nagomed, and then headed south to Sal'yany). South of Sal'yany the road follows the Osmanly Novyye - Astara railroad for a distance of 12 miles before

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

turning westward to Pushkino beyond the coastal region. The route then leads southward, passes through Astrakhan-Bazar, and enters the region at Pribibinskoye. From Pribibinskoye to Astara the route skirts the base of the Talysh Mountains, emerging at the coast only at Lenkoran' and Astara. Between Pribibinskoye and Lenkoran' there is an alternative route through less densely settled country which leads southeastward from Pribibinskoye to Kyyl-Agach and then runs within a mile of the coastline to Lenkoran'. From Lenkoran' to Astara the coastal road is partly gravel-surfaced and partly unimproved.

The Baku-Astara road differs in construction from section to section but along most of its extent it is sufficiently well built to be considered usable in all weather. For a distance of 35 miles southwest of Baku (to Pavlyany), the road is reported to be paved with asphalt; it may possibly be paved all the way to Alyaty. Postwar reports indicate that the stretch between Alyaty and Sal'yany has undergone a great deal of improvement. The road is apparently being resurfaced with compacted crushed rock and gravel. Parts which are not resurfaced become impassable to motorized vehicles after heavy or prolonged rains. South of Sal'yany the surface is predominantly crushed rock but some sections are asphalt paved. Major repairs are currently under way on the stretch between Lenkoran' and Astara.

In the northern part of the coastal region, where the foothills of the Great Caucasus Mountains approach the Caspian sea, the few improved roads and through routes are located near the sea coast. Unimproved, country roads which generally follow valleys and lowlands comprise the

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

vast bulk of the irregular road net. Only scattered stretches have been improved. Improvements usually consist of little more than grading or the application of a loose gravel surface. Traffic can move over these roads throughout the year. They become impassable to motorized vehicles for only short periods after rain or snowfalls. Horse-drawn traffic is rarely halted completely. Along the Caspian coast, in addition to the Baku - Astara road, a small net of improved roads winds through the petroleum bearing Kara-Dag area. These roads are gravel and sand surfaced and range between 15 and 25 feet in width.

In the central part of the region roads avoid the swampy and sandy coastal terrain and are concentrated at the region's western margin. There is a secondary concentration along the Kura River to the Caspian. The road net is comprised principally of unimproved roads and trails. The better roads have a surface of loose gravel or small stones. Along the Kura sand is also utilized as a surfacing material. The large, unpopulated swampy and sandy area northeast of the Kura is crossed by only a few trails. This area extends westward from the Caspian coast to the Alyaty - Sal'yany road; its northern limit lies in the vicinity of Khlydryly. A similar expanse, fronting on Zaliv Imeni Kirova, is located south of the Kura. The Alyaty - Sal'yany section of the Baku - Astara route, the Kazi-Magomed - Sal'yany road and the Sal'yany - Neftechala road are the principal through routes.

The Kazi-Magomed - Sal'yany, Sal'yany - Neftechala, and parts of the Alyaty - Sal'yany road are trafficable throughout the year. Most of the other roads become muddy and largely unsuitable for use from

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

mid-January until late March. However periods of muddiness continue to restrict movement until May.

The Sal'yary - Neftechala road is a recently improved, two lane road running along the right bank of the Kura. The road runs along an embankment and tends to follow the meanders of the Kura River. The entire route is probably surfaced with an asphalt-gravel mixture. On the outskirts of Neftechala oil derricks can be seen along both sides of the road.

In the southern part of the Baku - Astara Region the better roads are again found on the narrow coastal lowland. The Talysh Mountains have a very poor system of roads. The main roads of the Talysh run along the larger stream valleys to the coastal lowland. From north to south these valleys are the Vilyashchay (Velesh-Chay), Lenkoran' (Lenkoranka), Vesharyu, Tangyaryu, and the Astara-Chay. Numerous trails and short, narrow, dirt roads branch off the principal valley routes. There is very little integration of these individual valley road nets. Only the roads following the Vilyashchay, Lenkoran', and Astara-Chay Rivers appear to be improved. The Vilyashchay and Lenkoran' roads lead westward to the Soviet-Iranian frontier; the Astara-Chay road follows the international border. All are used for supplying frontier forces. Extensive repairs have been made on the Vilyashchay and Lenkoran' roads during the postwar years.

#### C. Water Transport

River transportation in the Baku - Astara Region is negligible, primarily because the rivers are short and shallow. Small boat traffic

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

of local importance moves only on the Kura River. Flat-bottomed boats drawing up to 3 feet of water can navigate the Kura at any time of the year. From April to June, small freighters and tugs can go as far as the town of Yevlakh, many miles west of the coastal region. Navigation along the lower course is greatly impeded by shifting sand bars. The busiest landing is at Sal'yany. Oil tankers plying the Caspian Sea operate regularly from Bol'shoy Orikat located near the mouth of the Kura.

The Caspian merchant fleet has shipping routes from Baku to three ports, Port Ilich, Lenkoran', and Astara. All are suitable only for small ships as approaches are shallow. Larger vessels must anchor 2 or 3 miles offshore and freight is ferried in by lighters. The principal articles of trade are lumber, fish and fish products, grain, and fruits. Lenkoran' and Astara have some degree of importance as ports of call for vessels engaged in trade with Iranian ports.

#### IX. Military Installations

The Baku - Astara Coastal Region is in general not heavily militarized but concentrations do exist at several points. The Baku petroleum fields located slightly to the north are strongly defended by anti-aircraft artillery. At least 6 airfields are also found on the Apsheron Peninsula. Within the region anti-aircraft positions are located at Lenkoran', Sal'yany, and possibly Neftechala. Small airfields are located near Alyaty, Pirsagat, Sal'yany, Neftechala, Lenkoran', and Astara. Astara also has a small seaplane anchorage. None appear to be currently of great importance. They are probably standby.

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

facilities which can be readily converted to fighter bases for the defense of the Baku petroleum area. The Alyaty field is probably now being used for pilot training. The fields at Neftechala, Lenkoran', and Astara are being used by civil airlines. They can handle only light transports.

The usual quota of border guards and installations is distributed along the Soviet-Iranian boundary. A regiment of troops is reported to be stationed at Astara.

Baku is a major operating base for the Soviet Navy's Caspian Flotilla, which is maintained primarily for training purposes. Most of the vessels attached to the flotilla are small consisting of units such as torpedo boats, gun boats, minesweepers, and patrol boats. The Caspian fleet also has submarines. The Soviet Naval Academy and a submarine training school are located near Baku. The offshore islands between Baku and the mouth of the Kura River are reported to be sites of naval activity. Naval exercises have been conducted in the Lenkoran' Astara vicinity.

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

X. Analyst's Note

The reliability of the information given in this report on inland terrain, vegetation, and climate ranges from good to excellent. The lack of recent maps and textual materials, however, precludes an accurate and complete terrain description of the shore and offshore islands.

Hydrographic information is incomplete, especially on the Caspian. Data on population, transportation, and military information are regarded as reliable but incomplete.

The place names used generally conform with those on the 1:250,000 orientation map. Sheet J-39-5 of the orientation map is a photo copy of an AMS provisional sheet. Consequently it is not accurate in scale. Another deficiency of this sheet is that the coastline of the Caspian was not corrected in compilation. As a result the southern sheet does not correspond to the others. Sheets of the Russian 1:100,000 series, based on surveys of the period 1936-1940, which are available at the Army Map Service Library, provide the largest scale map coverage for the region. The aerial photos, accompanying this report, are selected strips, showing the northern, south-central, and southern parts of the region. Series 1 (17 sheets, GX 1412 B, SK, 77-93) extends from Baku to Alyaty, Series 2 (16 sheets, GX 1990, SG, 72-87) from Ondzha-Kelya (5 miles west of Kyzyl-Agach) to Kholmili (on the coast 6 miles south of Lenkoran'), and Series 3 (6 sheets, GX 1990, SG, 57-62) from Mashkhan (about 2 miles south of Shekeran) to Astara. More extensive aerial photography is available at the Graphic Register of CIA.

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

S-E-C-R-E-T/C O N T R O L

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



Figure 1. Coastal plain south of Baku. Note steppe vegetation in the foreground. The clumps are probably wormwood.



Figure 2. Crater-like summit of mud volcano Lok Baton with oil field in the background.

S-E-C-R-E-T/C O N T R O L

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

S-E-C-U-R-I-T-Y/C O N T R O L

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3




Figure 2. A panoramic view of the southern coastal plain with the Talysh Mountains in the background. Soviet Astara is in the center and Iranian Astara is to the left.

S-E-C-U-R-I-T-Y/C O N T R O L

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

U.S.G.A.M./C O N T R O L

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



Figure 11. The straight coastline north of Ashara.

S E C R E T / C O N T R O L

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



Figure 5. Flat Kerkoraz plain extending northward from Iranian side of the Astara River.



Figure 6. Talysh Mountains rising steeply from the western side of the coastal plain near Astara.

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

S-E-C-R-E-T/C O N T R O L

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



Figure 7. The eastern Astara Valley and Soviet-Iranian frontier along the valley bottom.



Figure 8. Lower Kura River near the village of Yukhari-Khilly.

S-E-C-R-E-T/C O N T R O L

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



1. Small building near railway line. 2. Fence. 3. Cluster of trees. 4. Distant building.  
This photograph was taken from the Soviet side of the border control point  
at the railway station of Talysh.



Small buildings in dense forest cover on Talysh Mountain slopes in the  
Karakalpak Autonomous Republic.

SEARCHED/CONTROL



Figure 11. A village probably near the mouth of the Kura.



Figure 12. Bokorai street scene.

R.D.B. R.E.P./C.G.M.T.R.C.C.

Geographic/Political Control

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

CONFIDENTIAL



Figure 12. Soviet Astara as seen from Iranian Astara.

CONFIDENTIAL

Geographic/Political Control

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

7 5  
5046 CX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

GX1990F468SG

1.000 L.D.W.M. 5.200 m. 0.7 Stabja



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

387  
77  
04.6

GX1990F468SG

615  
y300  
RECORDED IN THE S.I.C. (M.D.O.X.H./SMA)

112  
Dad  
30.8.42  
2

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-2

GX1412B F403SK1425

b.d.l.


Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3  
2025 RELEASE UNDER E.O. 14176

**GX1412BF403SK172D**

ALICE Y. BRAZ MAILED

ZUPAI



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

WIDE ANGLE SAFETY FILM

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

100%  
100%

GX17122711035A1720

9703 : CIA-RDP79-01009A000500030001-3

COM

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

**GX1412B F403SK142B**

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

GXI412BFT403SK142B

93

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

KODAK SAFETY FILM

52

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

GX1412BF403SK/42B

2 Ob.d.L.

403 SK

83  
GX1412B F403SK/H2B

MUR YETTAH S-100

MUR YETTAH S-100

/05

1009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

A1412B F7903SK172B

2.0b

02

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

5381  
7 8  
594.3  
GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

3387  
7 9  
E043

GX1990F468SG



11 12  
0 9  
30.8 42  
2  
5

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

87  
2  
4,6  
GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

KODAK SAFETY FILM

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

7  
3  
6  
CX1990F468SG

12  
3 d 4  
0 8 42  
2  
6  
Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



GX1412B F403SK/42B

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

GX1412BF403SK142B

2Ob.d.L  
403 S


ENCL 2 SK 142B

base 200 09/03

2001/09/03 A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

103 SK



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 200

R 79-01009A000500030001-3

GX1412BF403SK/42B

Obd.I

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

587

4

GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

059  
f=504.6  
GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

CX1990F468SG

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

2000.1.17 PM 31/10/2012 13:40:00

5581  
81  
GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

587  
8  
4.6

GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

GX1990F468SG

12  
1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
4410  
4411  
4412  
4413  
4414  
4415  
4416  
4417  
4418  
4419  
4420  
4421  
4422  
4423  
4424  
4425  
4426  
4427  
4428  
4429  
4430  
4431  
4432  
4433  
4434  
4435  
4436  
4437  
4438  
4439  
4440  
4441  
4442  
4443  
4444  
4445  
4446  
4447  
4448  
4449  
4450  
4451  
4452  
4453  
4454  
4455  
4456  
4457  
4458  
4459  
4460  
4461  
4462  
4463  
4464  
4465  
4466  
4467  
4468  
4469  
4470  
4471  
4472  
4473  
4474  
4475  
4476  
4477  
4478  
4479  
4480  
4481  
4482  
4483  
4484  
4485  
4486  
4487  
4488  
4489  
4490  
4491  
4492  
4493  
4494  
4495  
4496  
4497  
4498  
4499  
44100  
44101  
44102  
44103  
44104  
44105  
44106  
44107  
44108  
44109  
44110  
44111  
44112  
44113  
44114  
44115  
44116  
44117  
44118  
44119  
44120  
44121  
44122  
44123  
44124  
44125  
44126  
44127  
44128  
44129  
44130  
44131  
44132  
44133  
44134  
44135  
44136  
44137  
44138  
44139  
44140  
44141  
44142  
44143  
44144  
44145  
44146  
44147  
44148  
44149  
44150  
44151  
44152  
44153  
44154  
44155  
44156  
44157  
44158  
44159  
44160  
44161  
44162  
44163  
44164  
44165  
44166  
44167  
44168  
44169  
44170  
44171  
44172  
44173  
44174  
44175  
44176  
44177  
44178  
44179  
44180  
44181  
44182  
44183  
44184  
44185  
44186  
44187  
44188  
44189  
44190  
44191  
44192  
44193  
44194  
44195  
44196  
44197  
44198  
44199  
44200  
44201  
44202  
44203  
44204  
44205  
44206  
44207  
44208  
44209  
44210  
44211  
44212  
44213  
44214  
44215  
44216  
44217  
44218  
44219  
44220  
44221  
44222  
44223  
44224  
44225  
44226  
44227  
44228  
44229  
44230  
44231  
44232  
44233  
44234  
44235  
44236  
44237  
44238  
44239  
44240  
44241  
44242  
44243  
44244  
44245  
44246  
44247  
44248  
44249  
44250  
44251  
44252  
44253  
44254  
44255  
44256  
44257  
44258  
44259  
44260  
44261  
44262  
44263  
44264  
44265  
44266  
44267  
44268  
44269  
44270  
44271  
44272  
44273  
44274  
44275  
44276  
44277  
44278  
44279  
44280  
44281  
44282  
44283  
44284  
44285  
44286  
44287  
44288  
44289  
44290  
44291  
44292  
44293  
44294  
44295  
44296  
44297  
44298  
44299  
44300  
44301  
44302  
44303  
44304  
44305  
44306  
44307  
44308  
44309  
44310  
44311  
44312  
44313  
44314  
44315  
44316  
44317  
44318  
44319  
44320  
44321  
44322  
44323  
44324  
44325  
44326  
44327  
44328  
44329  
44330  
44331  
44332  
44333  
44334  
44335  
44336  
44337  
44338  
44339  
44340  
44341  
44342  
44343  
44344  
44345  
44346  
44347  
44348  
44349  
44350  
44351  
44352  
44353  
44354  
44355  
44356  
44357  
44358  
44359  
44360  
44361  
44362  
44363  
44364  
44365  
44366  
44367  
44368  
44369  
44370  
44371  
44372  
44373  
44374  
44375  
44376  
44377  
44378  
44379  
44380  
44381  
44382  
44383  
44384  
44385  
44386  
44387  
44388  
44389  
44390  
44391  
44392  
44393  
44394  
44395  
44396  
44397  
44398  
44399  
44400  
44401  
44402  
44403  
44404  
44405  
44406  
44407  
44408  
44409  
44410  
44411  
44412  
44413  
44414  
44415  
44416  
44417  
44418  
44419  
44420  
44421  
44422  
44423  
44424  
44425  
44426  
44427  
44428  
44429  
44430  
44431  
44432  
44433  
44434  
44435  
44436  
44437  
44438  
44439  
44440  
44441  
44442  
44443  
44444  
44445  
44446  
44447  
44448  
44449  
44450  
44451  
44452  
44453  
44454  
44455  
44456  
44457  
44458  
44459  
44460  
44461  
44462  
44463  
44464  
44465  
44466  
44467  
44468  
44469  
44470  
44471  
44472  
44473  
44474  
44475  
44476  
44477  
44478  
44479  
44480  
44481  
44482  
44483  
44484  
44485  
44486  
44487  
44488  
44489  
44490  
44491  
44492  
44493  
44494  
44495  
44496  
44497  
44498  
44499  
44500  
44501  
44502  
44503  
44504  
44505  
44506  
44507  
44508  
44509  
44510  
44511  
44512  
44513  
44514  
44515  
44516  
44517  
44518  
44519  
44520  
44521  
44522  
44523  
44524  
44525  
44526  
44527  
44528  
44529  
44530  
44531  
44532  
44533  
44534  
44535  
44536  
44537  
44538  
44539  
44540  
44541  
44542  
44543  
44544  
44545  
44546  
44547  
44548  
44549  
44550  
44551  
44552  
44553  
44554  
44555  
44556  
44557  
44558  
44559  
44560  
44561  
44562  
44563  
44564  
44565  
44566  
44567  
44568  
44569  
44570  
44571  
44572  
44573  
44574  
44575  
44576  
44577  
44578  
44579  
44580  
44581  
44582  
44583  
44584  
44585  
44586  
44587  
44588  
44589  
44590  
44591  
44592  
44593  
44594  
44595  
44596  
44597  
44598  
44599  
44600  
44601  
44602  
44603  
44604  
44605  
44606  
44607  
44608  
44609  
44610  
44611  
44612  
44613  
44614  
44615  
44616  
44617  
44618  
44619  
44620  
44621  
44622  
44623  
44624  
44625  
44626  
44627  
44628  
44629  
44630  
44631  
44632  
44633  
44634  
44635  
44636  
44637  
44638  
44639  
44640  
44641  
44642  
44643  
44644  
44645  
44646  
44647  
44648  
44649  
44650  
44651  
44652  
44653  
44654  
44655  
44656  
44657  
44658  
44659  
44660  
44661  
44662  
44663  
44664  
44665  
44666  
44667  
44668  
44669  
44670  
44671  
44672  
44673  
44674  
44675  
44676  
44677  
44678  
44679  
44680  
44681  
44682  
44683  
44684  
44685  
44686  
44687  
44688  
44689  
44690  
44691  
44692  
44693  
44694  
44695  
44696  
44697  
44698  
44699  
44700  
44701  
44702  
44703  
44704  
44705  
44706  
44707  
44708  
44709  
44710  
44711  
44712  
44713  
44714  
44715  
44716  
44717  
44718  
44719  
44720  
44721  
44722  
44723  
44724  
44725  
44726  
44727  
44728  
44729  
44730  
44731  
44732  
44733  
44734  
44735  
44736  
44737  
44738  
44739  
44740  
44741  
44742  
44743  
44744  
44745  
44746  
44747  
44748  
44749  
44750  
44751  
44752  
44753  
44754  
44755  
44756  
44757  
44758  
44759  
44760  
44761  
44762  
44763  
44764  
44765  
44766  
44767  
44768  
44769  
44770  
44771  
44772  
44773  
44774  
44775  
44776  
44777  
44778  
44779  
44780  
44781  
44782  
44783  
44784  
44785  
44786  
44787  
44788  
44789  
44790  
44791  
44792  
44793  
44794  
44795  
44796  
44797  
44798  
44799  
44800  
44801  
44802  
44803  
44804  
44805  
44806  
44807  
44808  
44809  
44810  
44811  
44812  
44813  
44814  
44815  
44816  
44817  
44818  
44819  
44820  
44821  
44822  
44823  
44824  
44825  
44826  
44827  
44828  
44829  
44830  
44831  
44832  
44833  
44834  
44835  
44836  
44837  
44838  
44839  
44840  
44841  
44842  
44843  
44844  
44845  
44846  
44847  
44848  
44849  
44850  
44851  
44852  
44853  
44854  
44855  
44856  
44857  
44858  
44859  
44860  
44861  
44862  
44863  
44864  
44865  
44866  
44867  
44868  
44869  
44870  
44871  
44872  
44873  
44874  
44875  
44876  
44877  
44878  
44879  
44880  
44881  
44882  
44883  
44884  
44885  
44886  
44887  
44888  
44889  
44890  
44891  
44892  
44893  
44894  
44895  
44896  
44897  
44898  
44899  
44900  
44901  
44902  
44903  
44904  
44905  
44906  
44907  
44908  
44909  
44910  
44911  
44912  
44913  
44914  
44915  
44916  
44917  
44918  
44919  
44920  
44921  
44922  
44923  
44924  
44925  
44926  
44927  
44928  
44929  
44930  
44931  
44932  
44933  
44934  
44935  
44936  
44937  
44938  
44939  
44940  
44941  
44942  
44943  
44944  
44945  
44946  
44947  
44948  
44949  
44950  
44951  
44952  
44953  
44954  
44955  
44956  
44957  
44958  
44959  
44960  
44961  
44962  
44963  
44964  
44965  
44966  
44967  
44968  
44969  
44970  
44971  
44972  
44973  
44974  
44975  
44976  
44977  
44978  
44979  
44980  
44981  
44982  
44983  
44984  
44985  
44986  
44987  
44988  
44989  
44990  
44991  
44992  
44993  
44994  
44995  
44996  
44997  
44998  
44999  
441000  
441001  
441002  
441003  
441004  
441005  
441006  
441007  
441008  
441009  
441010  
441011  
441012  
441013  
441014  
441015  
441016  
441017  
441018  
441019  
441020  
441021  
441022  
441023  
441024  
441025  
441026  
441027  
441028  
441029  
441030  
441031  
441032  
441033  
441034  
441035  
441036  
441037  
441038  
441039  
441040  
441041  
441042  
441043  
441044  
441045  
441046  
441047  
441048  
441049  
441050  
441051  
441052  
441053  
441054  
441055  
441056  
441057  
441058  
441059  
441060  
441061  
441062  
441063  
441064  
441065  
441066  
441067  
441068  
441069  
441070  
441071  
441072  
441073  
441074  
441075  
441076  
441077  
441078  
441079  
441080  
441081  
441082  
441083  
441084  
441085  
441086  
441087  
441088  
441089  
441090  
441091  
441092  
441093  
441094  
441095  
441096  
441097  
441098  
441099  
441100  
441101  
441102  
441103  
441104  
441105  
441106  
441107  
441108  
441109  
441110  
441111  
441112  
441113  
441114  
441115  
441116  
441117  
441118  
441119  
441120  
441121  
441122  
441123  
441124  
441125  
441126  
441127  
441128  
441129  
441130  
441131  
441132  
441133  
441134  
441135  
441136  
441137  
441138  
441139  
441140  
441141  
441142  
441143  
441144  
441145  
441146  
441147  
441148  
441149  
441150  
441151  
441152  
441153  
441154  
441155  
441156  
441157  
441158  
441159  
441160  
441161  
441162  
441163  
441164  
441165  
441166  
441167  
441168  
441169  
441170  
441171  
441172  
441173  
441174  
441175  
441176  
441177  
441178  
441179  
441180  
441181  
441182  
441183  
441184  
441185  
441186  
441187  
441188  
441189  
441190  
441191  
441192  
441193  
441194  
441195  
441196  
441197  
441198  
441199  
441200  
441201  
441202  
441203  
441204  
441205  
441206  
441207  
441208  
441209  
441210  
441211  
441212  
441213  
441214  
441215  
441216  
441217  
441218  
441219  
441220  
441221  
441222  
441223  
441224  
441225  
441226  
441227  
441228  
441229  
441230  
441231  
441232  
441233  
441234  
441235  
441236  
441237  
441238  
441239  
441240  
441241  
441242  
441243  
441244  
441245  
441246  
441247  
441248  
441249  
441250  
441251  
441252  
441253  
441254  
441255  
441256  
441257  
441258  
441259  
441260  
441261  
441262  
441263  
441264  
441265  
441266  
441267  
441268  
441269  
441270  
441271  
441272  
441273  
441274  
441275  
441276  
441277  
441278  
441279  
441280  
441281  
441282  
441283

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

87  
4  
6  
GX1990F468SG

11 12  
10 9  
8 7  
6 5  
4 3  
2 1

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

10000  
60  
=504.6

MONDAY SEPTEMBER 14 1970

GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3


GX/4123 F403SK/42B

MJ11 YTB AG HANON



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3


85  
GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

82  
GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

MUR YT3A

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

MUR YT3B

3387  
8 6  
504.0

GX1990F468SG



Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

3387  
6  
504.6


GX1990F468SG



12  
11  
10  
9  
8  
7  
6  
5  
4  
3  
2  
1  
0  
Op.d.  
30.8.72

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3





Approved For Release 2001/09/03 : CIA-RDP79-01009A000500030001-3

SOUTHWESTERN ASIA 1:250,000

ARDABIL

Approved For Release 2001/09/03 : CIA-RDP79-01009A00500030001AMS


REFER TO THIS MAP AS:  
N.J. 39.5  
SERIES F202



CONTINUATION OF INTERNATIONAL BOUNDARIES ON THIS MAP ARE APPROXIMATE AND NOT ACCURATE.

THE DELINEATION OF INTERNATIONAL BOUNDARIES ON THIS MAP IS APPROXIMATE AND NOT ACCURATE.

Present to the Army Map Service (AMSA), Office of Engineers, U.S. Army, Washington, D.C. Compiled in 1952 from the following sources: 1:250,000 scale maps 39-29-1, 39-29-2, 39-29-3, 39-29-4, 39-29-5, 39-29-6, 39-29-7, 39-29-8, 39-29-9, 39-29-10, 39-29-11, 39-29-12, 39-29-13, 39-29-14, 39-29-15, 39-29-16, 39-29-17, 39-29-18, 39-29-19, 39-29-20, 39-29-21, 39-29-22, 39-29-23, 39-29-24, 39-29-25, 39-29-26, 39-29-27, 39-29-28, 39-29-29, 39-29-30, 39-29-31, 39-29-32, 39-29-33, 39-29-34, 39-29-35, 39-29-36, 39-29-37, 39-29-38, 39-29-39, 39-29-40, 39-29-41, 39-29-42, 39-29-43, 39-29-44, 39-29-45, 39-29-46, 39-29-47, 39-29-48, 39-29-49, 39-29-50, 39-29-51, 39-29-52, 39-29-53, 39-29-54, 39-29-55, 39-29-56, 39-29-57, 39-29-58, 39-29-59, 39-29-60, 39-29-61, 39-29-62, 39-29-63, 39-29-64, 39-29-65, 39-29-66, 39-29-67, 39-29-68, 39-29-69, 39-29-70, 39-29-71, 39-29-72, 39-29-73, 39-29-74, 39-29-75, 39-29-76, 39-29-77, 39-29-78, 39-29-79, 39-29-80, 39-29-81, 39-29-82, 39-29-83, 39-29-84, 39-29-85, 39-29-86, 39-29-87, 39-29-88, 39-29-89, 39-29-90, 39-29-91, 39-29-92, 39-29-93, 39-29-94, 39-29-95, 39-29-96, 39-29-97, 39-29-98, 39-29-99, 39-29-100, 39-29-101, 39-29-102, 39-29-103, 39-29-104, 39-29-105, 39-29-106, 39-29-107, 39-29-108, 39-29-109, 39-29-110, 39-29-111, 39-29-112, 39-29-113, 39-29-114, 39-29-115, 39-29-116, 39-29-117, 39-29-118, 39-29-119, 39-29-120, 39-29-121, 39-29-122, 39-29-123, 39-29-124, 39-29-125, 39-29-126, 39-29-127, 39-29-128, 39-29-129, 39-29-130, 39-29-131, 39-29-132, 39-29-133, 39-29-134, 39-29-135, 39-29-136, 39-29-137, 39-29-138, 39-29-139, 39-29-140, 39-29-141, 39-29-142, 39-29-143, 39-29-144, 39-29-145, 39-29-146, 39-29-147, 39-29-148, 39-29-149, 39-29-150, 39-29-151, 39-29-152, 39-29-153, 39-29-154, 39-29-155, 39-29-156, 39-29-157, 39-29-158, 39-29-159, 39-29-160, 39-29-161, 39-29-162, 39-29-163, 39-29-164, 39-29-165, 39-29-166, 39-29-167, 39-29-168, 39-29-169, 39-29-170, 39-29-171, 39-29-172, 39-29-173, 39-29-174, 39-29-175, 39-29-176, 39-29-177, 39-29-178, 39-29-179, 39-29-180, 39-29-181, 39-29-182, 39-29-183, 39-29-184, 39-29-185, 39-29-186, 39-29-187, 39-29-188, 39-29-189, 39-29-190, 39-29-191, 39-29-192, 39-29-193, 39-29-194, 39-29-195, 39-29-196, 39-29-197, 39-29-198, 39-29-199, 39-29-200, 39-29-201, 39-29-202, 39-29-203, 39-29-204, 39-29-205, 39-29-206, 39-29-207, 39-29-208, 39-29-209, 39-29-210, 39-29-211, 39-29-212, 39-29-213, 39-29-214, 39-29-215, 39-29-216, 39-29-217, 39-29-218, 39-29-219, 39-29-220, 39-29-221, 39-29-222, 39-29-223, 39-29-224, 39-29-225, 39-29-226, 39-29-227, 39-29-228, 39-29-229, 39-29-230, 39-29-231, 39-29-232, 39-29-233, 39-29-234, 39-29-235, 39-29-236, 39-29-237, 39-29-238, 39-29-239, 39-29-240, 39-29-241, 39-29-242, 39-29-243, 39-29-244, 39-29-245, 39-29-246, 39-29-247, 39-29-248, 39-29-249, 39-29-250, 39-29-251, 39-29-252, 39-29-253, 39-29-254, 39-29-255, 39-29-256, 39-29-257, 39-29-258, 39-29-259, 39-29-260, 39-29-261, 39-29-262, 39-29-263, 39-29-264, 39-29-265, 39-29-266, 39-29-267, 39-29-268, 39-29-269, 39-29-270, 39-29-271, 39-29-272, 39-29-273, 39-29-274, 39-29-275, 39-29-276, 39-29-277, 39-29-278, 39-29-279, 39-29-280, 39-29-281, 39-29-282, 39-29-283, 39-29-284, 39-29-285, 39-29-286, 39-29-287, 39-29-288, 39-29-289, 39-29-290, 39-29-291, 39-29-292, 39-29-293, 39-29-294, 39-29-295, 39-29-296, 39-29-297, 39-29-298, 39-29-299, 39-29-300, 39-29-301, 39-29-302, 39-29-303, 39-29-304, 39-29-305, 39-29-306, 39-29-307, 39-29-308, 39-29-309, 39-29-310, 39-29-311, 39-29-312, 39-29-313, 39-29-314, 39-29-315, 39-29-316, 39-29-317, 39-29-318, 39-29-319, 39-29-320, 39-29-321, 39-29-322, 39-29-323, 39-29-324, 39-29-325, 39-29-326, 39-29-327, 39-29-328, 39-29-329, 39-29-330, 39-29-331, 39-29-332, 39-29-333, 39-29-334, 39-29-335, 39-29-336, 39-29-337, 39-29-338, 39-29-339, 39-29-340, 39-29-341, 39-29-342, 39-29-343, 39-29-344, 39-29-345, 39-29-346, 39-29-347, 39-29-348, 39-29-349, 39-29-350, 39-29-351, 39-29-352, 39-29-353, 39-29-354, 39-29-355, 39-29-356, 39-29-357, 39-29-358, 39-29-359, 39-29-360, 39-29-361, 39-29-362, 39-29-363, 39-29-364, 39-29-365, 39-29-366, 39-29-367, 39-29-368, 39-29-369, 39-29-370, 39-29-371, 39-29-372, 39-29-373, 39-29-374, 39-29-375, 39-29-376, 39-29-377, 39-29-378, 39-29-379, 39-29-380, 39-29-381, 39-29-382, 39-29-383, 39-29-384, 39-29-385, 39-29-386, 39-29-387, 39-29-388, 39-29-389, 39-29-390, 39-29-391, 39-29-392, 39-29-393, 39-29-394, 39-29-395, 39-29-396, 39-29-397, 39-29-398, 39-29-399, 39-29-400, 39-29-401, 39-29-402, 39-29-403, 39-29-404, 39-29-405, 39-29-406, 39-29-407, 39-29-408, 39-29-409, 39-29-410, 39-29-411, 39-29-412, 39-29-413, 39-29-414, 39-29-415, 39-29-416, 39-29-417, 39-29-418, 39-29-419, 39-29-420, 39-29-421, 39-29-422, 39-29-423, 39-29-424, 39-29-425, 39-29-426, 39-29-427, 39-29-428, 39-29-429, 39-29-430, 39-29-431, 39-29-432, 39-29-433, 39-29-434, 39-29-435, 39-29-436, 39-29-437, 39-29-438, 39-29-439, 39-29-440, 39-29-441, 39-29-442, 39-29-443, 39-29-444, 39-29-445, 39-29-446, 39-29-447, 39-29-448, 39-29-449, 39-29-450, 39-29-451, 39-29-452, 39-29-453, 39-29-454, 39-29-455, 39-29-456, 39-29-457, 39-29-458, 39-29-459, 39-29-460, 39-29-461, 39-29-462, 39-29-463, 39-29-464, 39-29-465, 39-29-466, 39-29-467, 39-29-468, 39-29-469, 39-29-470, 39-29-471, 39-29-472, 39-29-473, 39-29-474, 39-29-475, 39-29-476, 39-29-477, 39-29-478, 39-29-479, 39-29-480, 39-29-481, 39-29-482, 39-29-483, 39-29-484, 39-29-485, 39-29-486, 39-29-487, 39-29-488, 39-29-489, 39-29-490, 39-29-491, 39-29-492, 39-29-493, 39-29-494, 39-29-495, 39-29-496, 39-29-497, 39-29-498, 39-29-499, 39-29-500, 39-29-501, 39-29-502, 39-29-503, 39-29-504, 39-29-505, 39-29-506, 39-29-507, 39-29-508, 39-29-509, 39-29-510, 39-29-511, 39-29-512, 39-29-513, 39-29-514, 39-29-515, 39-29-516, 39-29-517, 39-29-518, 39-29-519, 39-29-520, 39-29-521, 39-29-522, 39-29-523, 39-29-524, 39-29-525, 39-29-526, 39-29-527, 39-29-528, 39-29-529, 39-29-530, 39-29-531, 39-29-532, 39-29-533, 39-29-534, 39-29-535, 39-29-536, 39-29-537, 39-29-538, 39-29-539, 39-29-540, 39-29-541, 39-29-542, 39-29-543, 39-29-544, 39-29-545, 39-29-546, 39-29-547, 39-29-548, 39-29-549, 39-29-550, 39-29-551, 39-29-552, 39-29-553, 39-29-554, 39-29-555, 39-29-556, 39-29-557, 39-29-558, 39-29-559, 39-29-560, 39-29-561, 39-29-562, 39-29-563, 39-29-564, 39-29-565, 39-29-566, 39-29-567, 39-29-568, 39-29-569, 39-29-570, 39-29-571, 39-29-572, 39-29-573, 39-29-574, 39-29-575, 39-29-576, 39-29-577, 39-29-578, 39-29-579, 39-29-580, 39-29-581, 39-29-582, 39-29-583, 39-29-584, 39-29-585, 39-29-586, 39-29-587, 39-29-588, 39-29-589, 39-29-590, 39-29-591, 39-29-592, 39-29-593, 39-29-594, 39-29-595, 39-29-596, 39-29-597, 39-29-598, 39-29-599, 39-29-600, 39-29-601, 39-29-602, 39-29-603, 39-29-604, 39-29-605, 39-29-606, 39-29-607, 39-29-608, 39-29-609, 39-29-610, 39-29-611, 39-29-612, 39-29-613, 39-29-614, 39-29-615, 39-29-616, 39-29-617, 39-29-618, 39-29-619, 39-29-620, 39-29-621, 39-29-622, 39-29-623, 39-29-624, 39-29-625, 39-29-626, 39-29-627, 39-29-628, 39-29-629, 39-29-630, 39-29-631, 39-29-632, 39-29-633, 39-29-634, 39-29-635, 39-29-636, 39-29-637, 39-29-638, 39-29-639, 39-29-640, 39-29-641, 39-29-642, 39-29-643, 39-29-644, 39-29-645, 39-29-646, 39-29-647, 39-29-648, 39-29-649, 39-29-650, 39-29-651, 39-29-652, 39-29-653, 39-29-654, 39-29-655, 39-29-656, 39-29-657, 39-29-658, 39-29-659, 39-29-660, 39-29-661, 39-29-662, 39-29-663, 39-29-664, 39-29-665, 39-29-666, 39-29-667, 39-29-668, 39-29-669, 39-29-670, 39-29-671, 39-29-672, 39-29-673, 39-29-674, 39-29-675, 39-29-676, 39-29-677, 39-29-678, 39-29-679, 39-29-680, 39-29-681, 39-29-682, 39-29-683, 39-29-684, 39-29-685, 39-29-686, 39-29-687, 39-29-688, 39-29-689, 39-29-690, 39-29-691, 39-29-692, 39-29-693, 39-29-694, 39-29-695, 39-29-696, 39-29-697, 39-29-698, 39-29-699, 39-29-700, 39-29-701, 39-29-702, 39-29-703, 39-29-704, 39-29-705, 39-29-706, 39-29-707, 39-29-708, 39-29-709, 39-29-710, 39-29-711, 39-29-712, 39-29-713, 39-29-714, 39-29-715, 39-29-716, 39-29-717, 39-29-718, 39-29-719, 39-29-720, 39-29-721, 39-29-722, 39-29-723, 39-29-724, 39-29-725, 39-29-726, 39-29-727, 39-29-728, 39-29-729, 39-29-730, 39-29-731, 39-29-732, 39-29-733, 39-29-734, 39-29-735, 39-29-736, 39-29-737, 39-29-738, 39-29-739, 39-29-740, 39-29-741, 39-29-742, 39-29-743, 39-29-744, 39-29-745, 39-29-746, 39-29-747, 39-29-748, 39-29-749, 39-29-750, 39-29-751, 39-29-752, 39-29-753, 39-29-754, 39-29-755, 39-29-756, 39-29-757, 39-29-758, 39-29-759, 39-29-760, 39-29-761, 39-29-762, 39-29-763, 39-29-764, 39-29-765, 39-29-766, 39-29-767, 39-29-768, 39-29-769, 39-29-770, 39-29-771, 39-29-772, 39-29-773, 39-29-774, 39-29-775, 39-29-776, 39-29-777, 39-29-778, 39-29-779, 39-29-780, 39-29-781, 39-29-782, 39-29-783, 39-29-784, 39-29-785, 39-29-786, 39-29-787, 39-29-788, 39-29-789, 39-29-790, 39-29-791, 39-29-792, 39-29-793, 39-29-794, 39-29-795, 39-29-796, 39-29-797, 39-29-798, 39-29-799, 39-29-800, 39-29-801, 39-29-802, 39-29-803, 39-29-804, 39-29-805, 39-29-806, 39-29-807, 39-29-808, 39-29-809, 39-29-810, 39-29-811, 39-29-812, 39-29-813, 39-29-814, 39-29-815, 39-29-816, 39-29-817, 39-29-818, 39-29-819, 39-29-820, 39-29-821, 39-29-822, 39-29-823, 39-29-824, 39-29-825, 39-29-826, 39-29-827, 39-29-828, 39-29-829, 39-29-830, 39-29-831, 39-29-832, 39-29-833, 39-29-834, 39-29-835, 39-29-836, 39-29-837, 39-29-838, 39-29-839, 39-29-840, 39-29-841, 39-29-842, 39-29-843, 39-29-844, 39-29-845, 39-29-846, 39-29-847, 39-29-848, 39-29-849, 39-29-850, 39-29-851, 39-29-852, 39-29-853, 39-29-854, 39-29-855, 39-29-856, 39-29-857, 39-29-858, 39-29-859, 39-29-860, 39-29-861, 39-29-862, 39-29-863, 39-29-864, 39-29-865, 39-29-866, 39-29-867, 39-29-868, 39-29-869, 39-29-870, 39-29-871, 39-29-872, 39-29-873, 39-29-874, 39-29-875, 39-29-876, 39-29-877, 39-29-878, 39-29-879, 39-29-880, 39-29-881, 39-29-882, 39-29-883, 39-29-884, 39-29-885, 39-29-886, 39-29-887, 39-29-888, 39-29-889, 39-29-890, 39-29-891, 39-29-892, 39-29-893, 39-29-894, 39-29-895, 39-29-896, 39-29-897, 39-29-898, 39-29-899, 39-29-900, 39-29-901, 39-29-902, 39-29-903, 39-29-904, 39-29-905, 39-29-906, 39-29-907, 39-29-908, 39-29-909, 39-29-910, 39-29-911, 39-29-912, 39-29-913, 39-29-914, 39-29-915, 39-29-916, 39-29-917, 39-29-918, 39-29-919, 39-29-920, 39-29-921, 39-29-922, 39-29-923, 39-29-924, 39-29-925, 39-29-926, 39-29-927, 39-29-928, 39-29-929, 39-29-930, 39-29-931, 39-29-932, 39-29-933, 39-29-934, 39-29-935, 39-29-936, 39-29-937, 39-29-938, 39-29-939, 39-29-940, 39-29-9



Scale 1:250,000  
 0 5 10 15 20 25 30 Kilometers  
 0 5000 10000 15000 20000 25000 30000 Yards  
**CONTOUR INTERVAL, 100 METERS**  
**TRANSVERSE MERCATOR PROJECTION**  
 BLACK NUMBERS LOCATE THE 10,000 METER UNIVERSAL TRANSVERSE MERCATOR GRID.  
 THE LAST FOUR DIGITS OF THE GRID NUMBERS ARE OMITTED.  
 THIS MAP WAS RECORDED FOR THE U.S. COAST AND GEODYS. SURVEY, EASTERN DIVISION, IN 1940.  
 THE LAST FOUR DIGITS OF THE GRID NUMBERS ARE OMITTED.  
 THIS MAP WAS RECORDED FOR THE U.S. COAST AND GEODYS. SURVEY, EASTERN DIVISION, IN 1940.  
 USE WITH STATE PLANE COORDINATES, UTM, OR OTHER SYSTEMS.  
 THE CALCULATIONS FOR ELEVATION, DISTANCE, AREA, AND VOLUME ARE NOT ACCURATE.  
 CONSIDERATION OF ELLIPSOIDAL CURVATURE IS NOT MADE.